

KANSAS

FORM CP-3
Rev. 1-8-82STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORTRECEIVED
STATE CORPORATION COMMISSION
JUL - 7 1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15- -

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Pickrell Drilling Co.
 Complete Address 110 N. Market Suite 205 Wichita Kansas 67202
 Lease Name Astle Well No. "D" 1
 Location SW-SW-NE Sec. 33 Twp. 29 Rge. 22 (East) (West)
 County Ford Total Depth 5408'
 Abandoned Oil Well ☒ Gas Well ☒ Input Well ☐ SWD Well ☐ D&A ☐
 Other well as hereinafter indicated _____
 Plugging Contractor Kelso Casing Pulling
 Address Box 176 Chase Kansas 67524 License No. 681
 Operation Completed: Hour: 12:30 PM Day: 2 Month: July Year: 1982
 Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

The above well was plugged as follows:

They ran and cemented 5405' of 4 1/2" production pipe.
They plugged it back to 5373' & perforated the 4 1/2"
from 5285 to 5362. 1st plug sand back to 5230' & put 4 sbx
of cement on top of sand with baler. 2nd plug pumped through
8 1/8" head, 10 sbx jell, 5 sbx hulls & 15 sbx jell. Then released rubber
plug & followed it with 150 sbx of cement. They recovered
2500' of 4 1/2" pipe. The plugging was accomplished by
Allied Cementing. The cement was 50/50 Port with 2 1/2 jell 3 1/2 C.C.
 Amount of Surface Casing: 514' of 8 1/2" cemented with 300 sbx of cement.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division AgentINVOICED
DATE 7-8-82
INV. NO. 601-W