

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-057-20, 142-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Samuel Gary Oil Producer

Complete Address 100 Military Plaza, Dodge City Kans 67801

Lease Name Crew "A" Well No. 1

Location NE-NW Sec. 28 Twp. 29 Rge. 22 (East)(West)

County Ford Total Depth 5425'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Co.

Address Quatt Kans License No. _____

Operation Completed: Hour: 11:00 AM Day: 24 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They have 5400' of 5 1/2" production pipe set. They plugged back to 5360' and perforated at 5253' to 62'. They had a hole in production pipe at 804' so squeezed pipe with 125 lbs of class B cement under 2500 lbs pressure. They ran a bonding log on production pipe it was bonded from 726' to 858'. So they perforated production pipe at 720' and circulated water to top between surface casing & production pipe after setting cast iron plug. 1st plug pumped 25 lbs of cement on bottom with 2 lbs hulls ahead of cement (over)

Amount of Surface Casing: 304' of 8 1/2" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

STATE RECEIVED
MAR 27 1982
CONSERVATION DIVISION
Wichita, Kansas

3-26-82
9775-W
17b.3)

3-23-1982

2nd plug set cast iron plug at 820'. 3rd plug pumped
275 lbs of cement through production pipe filling both
the production pipe & surface casing to 0'. The plugging
was accomplished by Halliburton Co.