

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Lammal Gary Oil Producer

Complete Address #4 Everness Court East Englewood Colorado 80112-5599

Lease Name Rupp Well No. 11-13

Location SW-SW Sec. 11 Twp. 29 Rge. 22 (East) (West)

County Good Total Depth 5614'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated The well was completed but never produced

Plugging Contractor Sargants Casing Pulling

Address 6205 Lincoln Hwy 506 Liberal Kansas 67901 License No. 511

Operation Completed: Hour: 2:30 PM Day: 11 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 5594' of 4 1/2" production pipe cemented with cement
out side pipe to 4374'. The perforations are from 5270' to 75'
1st plug cemented bottom of hole with 25 bbl of cement.
2nd plug at 550' with 35 bbl of cement. 3rd plug at
40' to 0' with 10 bbl of cement. They recovered 2912' of
4 1/2" production pipe. The plugging was jumped
through production pipe - accomplished by
Sargants casing pulling.

Amount of Surface Casing: 554' of 8 1/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

3-16-1982

INVOICED

DATE 3-16-82

INV. NO. 9667-W