

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-057-20245-0000

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1981

CONSERVATION DIVISION
Wichita, Kansas

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Sam Gary Oil Co.

Complete Address 4 Swensen Court East Englewood Colo. 80112

Lease Name Honer Honer Well No. 10-7

Location C-5W-NE Sec. 10 Twp. 27S Rge. 22E (East)(West)

County Lord Total Depth 5335

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Salvarado Drilling Co. Rig #5

Address 435 Page Court 220 West Douglas Wichita, Kansas 67202 License No. _____

Operation Completed: Hour: 4:15 AM Day: 4 Month: November Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 575' of 8" surface casing cement circulated. The anhydrite was topped at 1776'. All fresh water formations are behind the surface casing. 1st plug at 1380' with 70 sbs. cement. 2nd plug pushed rubber plug to 550' and put 40 sbs. of cement on top of it. 3rd plug on solid bridge at 40' to 0' with 10 sbs. cement. Then 5 sbs. of cement pumped into rat hole. Plugging accomplished by Halliburton Co. out of Pratt, KS.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luther
Conservation Division Agent

INVOICED
DATE 12-11-81
TRV. NO. 8645-W