

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-057-20257-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Lee Banks Oil Co.

Complete Address 200 W. Douglas Suite 550 Wichita Kansas 67202

Lease Name F. L. Co. Well No. 1

Location C-NW-NW Sec. 35 Twp. 29 Rge. 26 (East)(West)

County Ford Total Depth 5336'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor D. R. Louch Oil Co. Inc.

Address 221 S. Broadway Suite 400 Wichita, Kans. 67202 License No. _____

Operation Completed: Hour: 2:45 P.M. Day: 25 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 1420'. 1st plug at 1280' with 60 bbl of cement. 2nd plug at 600'. Pushed rubber plug to 600' and pumped 50 bbl of cement on top of it. 3rd plug 40' to 0' on solid bridge with 10 bbl of cement. Then circulated 10 bbl of cement in rat hole & 3 bbl of cement in water well. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Allied Cementing.

Amount of Surface Casing: 611' of 8 7/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I didn't take the word on time of plugging to make it to well. But checked the well on way home. I feel this well was plugged right because I got a lot of faith in the crew on this rig. I have been on to many wells with them to believe differently.

Signed: Paul A. Luthi
Conservation Division Agent

DATE 4-7-82
INV. NO. 9884W

MAR 30 1982
CONSERVATION DIVISION
Wichita Kansas