

1 030797

5-3-87
15-047-20398-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion 6/30/77

SW SW SE, SEC. 23, T 28 S, R 18 (W/E)

330 feet from S section line
2270 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name Hardy B Well # 2

Operator: Chevron U.S.A. Inc.
Name & Address: P.O. Box 12116
Oklahoma City, OK 73157

County Kiowa 157.63
Well Total Depth 4850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 2 Month: 5 Year: 19 87

Plugging proposal received from Tony Halan

(company name) Chevron U.S.A. Inc. (phone) 405-949-7000

were: 5 1/2" at 4843' Open Hole 4843-50'

1st plug set cement retainer at 4800' - squeeze with 25 sx Class H cement - 5 sx cement

on top of retainer, 2nd plug perforate at 1650' - squeeze with 100 sx cement,

3rd plug backside - fill 5 1/2" from 1650-0' - 4th plug pump 100 sx cement down annulus.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 3 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug perforate at 1650' - squeeze with 190 sx cement,

2nd plug squeeze annulus - cement return outside surface pipe - shut down,

3rd plug squeeze 5 1/2" with 80 sx cement and displace with water to 1250' - shut in overnight,

4th plug perforate at 450' - circulate cement to surface with 130 sx Class A cement.

Remarks: No recovery. Used Class H and Class A cement by Halliburton.
(If additional description is necessary, use BACK of this STATE CORPORATION COMMISSION

RECEIVED

INVOICED observe this plugging.

Signed Steve Durrant MAY 11 1987 5-11-87

(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

DATE 5-15-87

INV. NO. 16893