

To: 1 061096
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-14-88 95A
API NUMBER 15-097-10094-0000

C E/2 SE, SEC. 23, T 28 S, R 18 W/E
1320 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corporation
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

Lease Name Hardy "E" Well # 1
County Kiowa 17/11
Well Total Depth 5265 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Clarke Corporation License Number 5105

Address: Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:30 p.m. Day: 14 Month: 4 Year: 1988

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4957' PBTB 4350' Perfs at 4264-68'
1st plug sand back to 4218' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 14 Month: 4 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4218' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 450 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 97888 Titan. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

APR 19 1988

DATE 4-26-88

INV. NO. 20474

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luttici (TECHNICIAN)