

To: 1 040749  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-22 API NUMBER 15-15-697-20987-00-01 Drilled 2/9/84 28R

SE SE NE, SEC. 10, T 28 S, R 18 W/EX

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Einsel J Well # 1

Operator: Marathon

County Kiowa

Name & Address RR 1, Box 25

Well Total Depth 4890 158.92 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5165

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:45 p.m. Day: 22 Month: 3 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4877' w/250 sx cement, PBD 4864', Perfs at 4820-32, 4801-07'

1st plug sand back to 4750' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 150' sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 p.m. Day: 22 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 4 sx cement on top of sand

bridge through bailer,

Operator had some drilling mud in pit he needed to get rid of, so he used it in place of mud.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 30 bbls. drilling mud, 50 sx

cement, 30 bbls. drilling mud, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150' sx cement.

Maximum pressure 800 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3112' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form Wichita, Kansas)

**INVOLVED**

I (and ~~XXXXXXX~~) observe this plugging.

DATE 3-29-93

INV. NO. 37519

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1993  
3-26-93  
CONSERVATION DIVISION  
Wichita, Kansas