

15-097-0032-00-01

Original spud 12-1-57
OWWO Spud 4-14-83

1 060816

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SW, SEC. 9, T 28 S, R 18 W/8
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Rosenberger Well # 1

Operator: TXO Production Corporation
Name & Address: 155 N. Market, Suite 1000
Wichita, KS 67202

County Kiowa 160.88
Well Total Depth 4950 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:00 am Day: 28 Month: February Year: 19 86

Plugging proposal received from Jerry Pritchert

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 4949' PBTD 4820' Perfs at 4830-39'

1st plug sand back to 4698' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4698' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 400 psi

Remarks: Recovered 2436' 4 1/2" casing. Used 50/50 Pozmix 2% gel by Dowell.
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

MAR 04 1986

STATE CORPORATION COMMISSION

Signed Paul A. Luthi
(TECHNICIAN)

DATE

MAR 4 1986

3-4-86

INV. NO. 12858
2-28

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84