

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,981-0000

NW/4 Sec. 7, T 28 S, R 18 W/4

2310 feet from N/4 section line

330 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8482

Lease Name DAVIS Well # 1-7

Operator: SAVELLA & STULL  
Name & Address 3131 BELL, SUITE 200  
AMARILLO, TX 79106

County KIOWA

Well Total Depth 5000 feet 162.50

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Surface Casing: Size 8 5/8 feet 477

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor EAGLE DRILLING, INC. License Number 5380

Address P.O. Box 8609, WICHITA, KS 67208

Company to plug at: Hour: 9 pm. Day: 4 Month: JAN Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Butch Stinert

(company name) Eagle (phone) \_\_\_\_\_

were: to use 60/40 Pozmix, w/ 2% gel - 3% CC AND SPOT  
the 1<sup>ST</sup> plug @ 1170' w/ 50 sy - 2<sup>ND</sup> plug @ 660' w/ 70 sy  
3<sup>RD</sup> plug @ 40' w/ solid bridge, plug and 10 sy.  
Circulate 15 sy in the rat hole and 10 sy  
in the mouse hole. Pull pump and plug water well  
w/ 5 sy.

Signed R Barluttan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:30 AM Day: 5 Month: JAN Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered.  
Cementing by Halliburton.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (~~did~~/ did not) observe this plugging.

1-13-84

Signed R Barluttan  
(TECHNICIAN)

INVOICE  
DATE 1-16-84  
INV. NO. 9114-W