

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-26925-0006
NW, Sec. 7, T 28 S, R 18 W/E
1980 feet from N/E section line
1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7306

Lease Name DAVIS Well # 1
County Kiowa
Well Total Depth 4960 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 451

Operator: Cinco Exploration Comp.
Name & Address 3935 Hartsdale
Houston Texas 77063

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well License Number 5893
Address Box 847 Pratt, KS 67124

Company to plug at: Hour: 3:30 pm Day: 24 Month: Feb Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Gus Trojack
(company name) Cinco Exploration Company (phone) _____

were: Mud bottom of hole + set Cast Iron Bridge plug at 4200'

2nd Plug 3 hulls - 15 gel - 70sx - 10 gel - 1 hull -
1 Plug - 125sx Cement
50/50 poz mix 4% gel 3% cc

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 pm Day: 24 Month: Feb Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph.
Recovered 2500' of 4 1/2" production casing
Maximum Pump pressure 600 psi
Shot in Pressure 200 psi
Haliburton did the cementing work

Remarks: Mr. Steve Durrant gave the plugging orders
Perforations at 4252' to 4256'

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

STATE CORPORATION COMMISSION
RECEIVED
MAY 3 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED
DATE 3-24-83
INV. NO. 3597-W

3-3-83