

To: 1 060730  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-21,157-0002  
C-SW-SE, SEC. 287, T 28 S, R 18 W/E  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Weir Well # 1

Operator: Oil Producers Inc. of Kansas County Waver 159.58  
Name & Address 1346 N. Woodlawn Box 8647  
Wichita, Kans

Well Total Depth 4910 feet

Production Conductor Pipe: Size 4 1/2 feet 4909

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated Perforations 4806' to 4816'

Plugging Contractor Great Bend Casing Pulling Co. License Number 4635

Address Box 768 Great Bend Kansas 67530

Company to plug at: Hour: 9:30 AM Day: 20 Month: November Year: 1985

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pulling Co. (phone) 316-793-9721

1st plug Pump 50 lbs cent + stop plug @ 4700'  
2nd plug pumps 3 lbs bull + 15 lbs gell + 50 lbs cent + 10 lbs gells + 1 lbs bull + release wood plug + pump 100 lbs cent.

Plugging Proposal Received by Paul A. Luttie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:15 AM Day: 20 Month: November Year: 1985

ACTUAL PLUGGING REPORT

1st plug pumped 50 lbs cent down 4 1/2" pipe  
and stopped plug @ 4700'. 2nd plug squeezed 8 5/8" w/ 3 lbs bull  
+ 15 lbs gell + 50 lbs cent + 10 lbs gells + 1 lbs bull + released wood  
plug + pumped 100 lbs cent. Max pressure 400# shut in  
w/ 100# pressure. Allied pumped 60/40 pass mix w/  
6% gell. They had recovered 3188' of 4 1/2" production pipe.

Remarks: \_\_\_\_\_  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE DEC 10 1985

INV. NO. 11366

DEC 2 1985  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Paul A. Luttie  
(TECHNICIAN)