

To: 1 041258 7-10
STATE CORPORATION COMMISSION
Wichita, State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 097-21,053-0000
C NE NW, SEC. 26, T 28 S, R 17 WXX
4620 feet from S section line
3300 feet from E section line
Lease Name Wheeler Well # 1-26
County Kiowa 160.88
Well Total Depth 4950 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 480

TECHNICIAN'S PLUGGING REPORT
Operator License # 31872
Operator: Paleozoic Prospects, Inc.
Name & Address P.O. Box 780002
Wichita, KS 67278-0002

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____
Plugging Contractor Pratt Well Service Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 11 a.m. Day: 10 Month: 7 Year: 19 97
Plugging proposal received from Fred Mease
(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 4 1/2" at 4950' w/250 sx cement, Perfs at 4240-43'
1st plug set CIBP at 4150' with 2 sx cement on top,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

7-16-97

RECEIVED
MAIL ROOM
AUG 11 1997

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:45 a.m. Day: 10 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4200' and dumped 2 sx cement on top of CIBP through
dump bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 750 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. Perfer (TECHNICIAN)

DATE 7-18
INV. NO. 48603
7-10