

To: 1031494

3-21

API NUMBER 15-097-21,430-0000

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION 150' N C N/2 NE SEC. 19, T 28 S, R 17 W/EX  
130 S. Market, Room 2078  
Wichita, KS 67202

510 feet from NE section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6926

Lease Name Wynona Ross Well # 2

Operator: Advantage Resources, Inc.  
Name & Address 1775 Sherman St., Ste. 1900  
Denver, CO 80203-4316

County Kiowa 159.90

Well Total Depth 4920 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 462

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 21 Month: 3 Year: 19 98

Plugging proposal received from Joe Livingston

(company name) Duke Drilling Co. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1140' with 50 sx cement, 2nd plug at 480' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Fill water well w/cement. Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:15 p.m. Day: 21 Month: 3 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug at 1140' with 50 sx cement,

2nd plug at 480' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement,

Water well filled with 10 sx cement to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

I (xxx / did not) observe this plugging.  
DATE 3-30-98  
INV. NO. 50324

Signed Steve Durrant (TECHNICIAN)

RECEIVED  
STATE OF KANSAS  
MAY 26 1998

3-26-98

INVOICED

1120

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 3-9-98  
DISTRICT # 1  
SGA? Yes X No

State of Kansas 097-21,430-0000

FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Expected Spud Date March 6, 1998  
month day year

Spot 150' N of East  
C. N/2. NE. Sec. 19. Twp. 28S S, Rg. 17W. West

OPERATOR: License # 6926  
Name: ADVANTAGE RESOURCES, INC.  
Address: 1775 Sherman Street, Suite 1900  
City/State/Zip: Denver, Colorado 80203-4316  
Contact Person: Lou Rottz  
Phone: 303/831-1972

510 feet from SW 1/4 North line of Section  
1320 feet from East 1/2 line of Section  
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Kiowa  
Lease Name: WYNONA ROSS Well #: 2  
Field Name: HARRY  
Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): LANING, MISSISSIPPI  
Nearest lease or unit boundary: 510

CONTRACTOR: License #: 5929  
Name: DUKE DRILLING CO., INC.

Ground Surface Elevation: 2211 feet MSL  
Water well within one-quarter mile: X yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 180'  
Depth to bottom of usable water: 220'  
Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 450'  
Length of Conductor pipe required: N/A  
Projected Total Depth: 4900  
Formation at Total Depth: KANSAS ROCK  
Water Source for Drilling Operations:  
X well farm pond other

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec X Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWMO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
If OWMO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location:

Will Cores Be Taken? yes X no  
If yes, proposed zone:

Exp. 9/4/98

240' Alt. I Req.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Joe King to J  
SPUD DATE 3-13-98 INIT. JW  
LENGTH SURFACE PLANNED 450'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLE AHEAD? Y N SIZE HOLE  
SURFACE PIPE 5 1/2" CONDUCTOR  
ANHYDRITE T-B-462 ELEVATION  
TD 4920 FORMATION  
RAN PIPE @ 4900 DV TOOL ALT II DONE  
SX Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
Anhydrite Base @ 1140 Ft. W/ 50 SX  
1/2 Base Anyh. @ Ft. W/ SX  
1/2, 1/2 Plug @ Ft. W/ SX  
2 Bottom Surface @ 480 Ft. W/ 50 SX  
3 40' Plug @ 40-0 Ft. W/ 10 SX  
RAT HOLE CIRC/W 1 5 SX MOUSE HOLE W/ 10 SX  
WATER WELL Yes - Rozen Grant - Bemis Pond  
Hauling  
TECHNICIAN SP DATE 3-20-98  
TYPE OF CEMENT 6/460  
STARTING TIME 7: (AM/PM) DATE 3-21  
COMPLETION TIME 8: 15 (AM/PM) DATE 3-21-98  
CEMENT COMPANY Allied 5886