

1 030254

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,948 -6600
SE SE , SEC. 36 , T 28 S, R 16 W/E
660 FSL N SE Corner of
feet from ~~XXX~~ section line
660 FEL W SE Corner of
feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8819
Operator: Cinco Energy Company
Name & Address: P. O. Box 3723
Victoria, TX 77903-3723

Lease Name Machesney Well # 2
County Kiowa
Well Total Depth 4820 156.65 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 474

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:00 am Day: 21 Month: August Year: 19 84

Plugging proposal received from Elmo Morgenstern
(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 4819' PBDT 4775' Perfs 4674-81'

1st plug sand back to 4620' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump additional 150 sx cement.

Plugging Proposal Received by Steve Belmont (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 21 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4819' PBDT 4775' Perfs 4674-81'

1st plug sanded back to 4620' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in pressure 250 psi AUG 24 1984

Remarks: Recovered 3510' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by _____
(If additional description is necessary, use BACK of this form. Wichita, Kansas)

INVOICED

8-29-84

Signed Steve Belmont (TECHNICIAN)

8-24-84 SD

INV. NO. 3408