

1 020152

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,032-0000

C NE NW, SEC. 25, T 28 S, R 16 W

1980 feet from ~~XXX~~/S section line

1980 feet from ~~WXX~~ section line

Robins Trust -

Lease Name Hughes Well # 1

County Kiowa

Well Total Depth 4750 154.38 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 328

TECHNICIAN'S PLUGGING REPORT

Operator License # 5237

Operator: Plano Petroleum Corp.

Name & Address P. O. Box 247

Plano, TX 75074

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address 453 South Webb Road, # 100, Wichita, KS 67207

Company to plug at: Hour: 9:00 pm Day: 5 Month: May Year: 19 84

Plugging proposal received from Mark Gwinn

(company name) Aldebaran (phone) 316-672-7471

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 795' with 50 sx cement

2nd plug at 380' with 50 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by *Tom Wilbur* (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 pDay: 5 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 795' with 50 sx cement, 2nd plug at 380' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug to circulate

mousehole with 10 sx cement. Plug water well with 5 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun B.J.

(If additional description is necessary, use BACK of this form.)

(Solid / dig not) observe this plugging.

INVOICED

DATE 5-15-84

INV. NO. 1507

Signed *Tom Wilbur* (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1984
CONSERVATION DIVISION
Wichita, Kansas