

1 010167

20346

169  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER ~~15- 097-20,326-A-00-01~~  
C NE NE, SEC. 22, T 28 S, R 16 W/X  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Ruch (OWWO) Well # 1

Operator: TXO Production Corporation  
Name & Address: 155 N. Market, Suite 1000  
Wichita, KS 67202

County Kiowa 118.07

Well Total Depth 3633 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 456

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor TXO Production Corporation License Number 5171

Address 155 N. Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 10:15 a.m. Day: 29 Month: 8 Year: 1986

Plugging proposal received from Jerry Collins

(company name) TXO (phone) 316-265-9441

were: 4 1/2" at 3602' PBTD 3587

1st plug sand back to 3420' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls with water mixed, 2 sx hulls with 100 sx cement.

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 8 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3420' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls with water mixed, 2 sx hulls with 100 sx of thrifty mix-weight of 12.5 lbs.

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Recovered 2200' of 4 1/2" casing. Used thrifty mix (weight 12.5 lbs.) by B.J. Titan (If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 9-3-86  
INV. NO. 14873

Signed Jack Luthi (TECHNICIAN)

SEP 31 1986