

To: 1 040262
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corporation
Name & Address: 1660 Lincoln Street, Suite 1800
Denver, CO 80264

4-5
API NUMBER 15-097-20,791-A00-01

C NE NW, SEC. 20, T. 28 S, R. 16 W/E
4620 feet from S section line
3300 feet from E section line

Lease Name Bergner Well # 1

County Kiowa 11892

Well Total Depth 3659 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 413

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 5 Month: 4 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3658' RBTD 3603' Perfs at 3524-26'

1st plug sand back from 3603-3475' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1050',

3rd plug pump 50 sx cement at 450',

4th plug pump 10 sx cement at 40'.

RECEIVED

STATE CORPORATION COMMISSION

APR 11 1989

4-11-89

Plugging Proposed by Steve Pfeifer
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 p.m. Day: 5 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back from 3603-3475' and dump 4 sx cement on top

of sand through bailer, spotted plugs through 2 3/8" tubing, loaded hole with gel,

2nd plug at 1050' with 50 sx cement,

3rd plug at 450' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2550' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 4-24-89
INV. NO. 24462