

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21204-00-00
Spot: CNWNWNW Sec/Twnshp/Rge: 16-28S-16W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: DEAN Well Number: 1
County: KIOWA Total Vertical Depth: 4802 feet

Operator License No.: 31000 Conductor Pipe: Size _____ feet: 8156-07
Op Name: PRATER OIL & GAS OPERATIONS, INC. Surface Casing: Size 8.625 feet: 410 WITH 300 SX CMT
Address: 906 WILLIAM WAY Production: Size 4.5 feet: 4794 WITH 125 SX CMT
PRATT, KS 67124 Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2002 11:15 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND BACKT O 4650' & 4 SX CMT ON TOP. 1ST PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/26/2002 12:15 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4708-12 & 4722-32'. 2 3/8" TUBING HUNG UP. GOT TUBING LOOSE & STARTED TO LAY DOWN TUBING. TUBING HUNG UP AGAIN (BOTTOM OF TUBING AT APPROX. 4080') UNABLE TO GET TUBING LOOSE. BROKE CIRCULATION WITH PUMP TRUCK. CIRCULATED HEAVY DRILLING MUD OUT OF HOLE. MUD INDICATION OF CASING LEAK AT UNDETERMINED DEPTH. PUMPED BOTTOM PLUG THROUGH 2 3/8" TUBING WITH 50 SX COMMON CMT. UNABLE TO GET SHOT ANY DEEPER THAN 2500' INSIDE 2 3/8" TUBING (SOME CORK SCREWED JOINTS IN TUBING STRING). SHOT 2 3/8" TUBING OFF AT 2500' & LAID DOWN TUBING. ESTIMATE APPROX. 1580' OF 2 3/8" TUBING & POSSIBLY PACKER LEFT IN HOLE. TOP OF TUBING AT 2500' & BOTTOM AT APPROX. 4080'. PUMPED DOWN 2 3/8" TUBING WITH 50 SX CMT COMMON CMT. DISPLACED CMT TO 4100'. LAID DOWN 4 1/2" CASING & RUN 2 3/8" TUBING IN TO PLUG THROUGH. 1ST PLUG AT 1100' WITH 12 SX GEL & 50 SX CMT WITH 100# HULLS MIXED IN. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED

AUG 07 2002 8-7-02

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2460' OF 4-1/2" CASING.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

JUL 29 2002

DATE 8-7-02

INV. NO. 2003060181