

1 060815

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,360-0000

NW NW NE, SEC. 15, T 28 S, R 16 W/NE
4850 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Dilg Well # 1

Operator: TXO Production Corp.
Name & Address 155 North Market, Suite 1000
Wichita, KS 67202

County Kiowa 156.65
Well Total Depth 4820 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 452

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:00 pm Day: 28 Month: February Year: 19 86

Plugging proposal received from Jerry Pritchert

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 4819' PBD 4600' Perfs at 4668-76'

1st plug sand back to 3433' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3433' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

Maximum pressure 700 psi and shut in 400 psi

Remarks: Recovered 2660' 4 1/2" casing. Used 50/50 Pozmix 2% gel by Dowell.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

STATE CORPORATION COMMISSION

Signed

Paul A. Luthi
(TECHNICIAN)

DATE MAR 04 1986

MAR 4 1986

INV. NO. 12857

CONSERVATION DIVISION
Wichita, Kansas

3-4-86

FORM CP-2/3
Rev. 01-84