

1060155

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,259-0000

SEC. 15, T 28 S, R 16 W/E

1320 feet from N/SX section line

330 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Schaul Well # 1

Operator: TXO Production

County Kiowa

Name & Address 200 West Douglas

Well Total Depth 4724 153.53 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:00 pm Day: 10 Month: February Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: PBDT 4702 Perfs 4686 to 94 4 1/2" set at 4730 with 130 sx cement

1st plug pumped 35 sx cement to bottom, 2nd plug 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and pumped additional 125 sx cement.

Maximum pressure 700# and shut-in pressure 300#

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:00 pm Day: 10 Month: February Year: 19 84

ACTUAL PLUGGING REPORT PBDT 4702 Perfs 4686 to 94 4 1/2" set at 4730 with 130 sx cement.

1st plug pumped 35 sx cement to bottom. 2nd plug 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and pumped an additional 125 sx cement. Maximum pressure 700# and shut-in pressure 300#

Remarks: They recovered 2600' production pipe. Use 60/40 Pozmis 2% gel, 3% cc. by Sun (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-22-84

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 0311