

1 040065

3-14-88

API NUMBER 15-097-20,402-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NE, SEC. 2, T 28 S, R 16 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Lease Name Grimm Well # 1-2

Operator: ONEOK Exploration

County Kiowa 152.04

Name & Address RR 1, Box 122A

Well Total Depth 4678 feet

E1 Reno, OK 73036-9702

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:15 p.m. Day: 14 Month: 3 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4677' PBSD 4675' Perfs at 4635-37'

1st plug sand back from 4675-4585' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1 p.m. Day: 14 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4585' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

MAR 23 1988

Maximum pressure 600 psi and shut in 200 psi.

3-23-88

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

(If applicable) observe this plugging.

DATE 3-25-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 20207

Billing Address

American Energy Recovery
P.O. Box 32349
Oklahoma City, Okla. 73123