

3-30-88

API NUMBER 15- 097-20,446-0000

To: 1 061087
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 50' NW C SW, SEC. 2, T 28 S, R 16 WAE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1345 feet from S section line
3985 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548
Operator: ONEOK Exploration
Name & Address: RR 1, Box 122A
El Reno, OK 73036-9702

Lease Name Binford Well # 1-2
County Kiowa 152.85
Well Total Depth 4703 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 30 Month: 3 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4702' PBSD 4673' Perfs at 4638-46' Elevation 2114' KB

1st plug sand back to 4588' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 30 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4588' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 800 psi and shut in 450 psi. 4-1-88 APR - 1 1988

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi (TECHNICIAN)

INVOICED (do not) observe this plugging.

DATE 4-5-88

INV. NO. 20794