

1 040063

3-14-88

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,652-0000

SE SE SW, SEC. 2, T 28 S, R 16 W/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Lease Name Binford Well # 2-2

Operator: ONEOK Exploration

County Kiowa 153.73

Name & Address RR 1, Box 122A

Well Total Depth 4730 feet

El Reno, OK 73036-9702

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 373

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 14 Month: 3 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4729' PBSD 4700' Perfs at 4667-73' Elevation 2107' GL

1st plug sand back from 4700' to 4617' with 4 sx cement with bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 a.m. Day: 14 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4617' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 100 psi.

3-23-88  
MAR 23 1988

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED

(do not ~~XXXXXX~~) observe this plugging.

DATE 3-25-88

Signed Stephan P. Pfeifer  
(TECHNICIAN)

INV. NO. 20205

Billing Address

American Energy Recovery

P.O. Box 32349

Oklahoma City, Okla. 73123