

1 060948

APR 16 1987 15-097-20664-0000 93

API NUMBER 15- Completion Date 8/25/80

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SE, SEC. 2, T 28 S, R 16 W/E

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Lease Name Stroud Well # 1-2

Operator: Oneok Exploration Company

County Kiowa 156.00

Name & Address Box 784

Well Total Depth 4800 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8 a.m. Day: 16 Month: 4 Year: 19 87

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4799' PBSD 4782' Perfs at 4667-77'

1st plug sand back to 4615' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 5 sx gel, 150 sx cement.

Plugging Proposal Received by Don Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9 a.m. Day: 16 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4615' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 5 sx gel, released 8 5/8" wiper plug and pumped 150 sx cement.

4-20-87

RECEIVED

STATE CORPORATION COMMISSION

Maximum pressure 600 psi and shut in 150 psi.

APR 20 1987

Remarks: Recovered 2540' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 4-21-87

INV. NO. 16591