

3-14-88

1 040064

API NUMBER 15- 097-20,719-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SE NW, SEC. 2, T 28 S, R 16 W/E  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Lease Name Grimm Unit Well # 2-2

Operator: ONEOK Exploration  
Name & Address: RR 1, Box 122A  
El Reno, OK 73036-9702

County Kiowa 156.20  
Well Total Depth 4806 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:15 a.m. Day: 14 Month: 3 Year: 1988

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4805' PBD 4776' Perfs at 4628-33'

1st plug sand back to 4578' with 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 14 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4578' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 3-25-88

INV. NO. 20204

Signed Stephen Pfeifer (TECHNICIAN)

Billing Address

American Energy Recovery  
P.O. Box 32349  
Oklahoma City, Okla. 73123