

To: 1090018
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-17
API NUMBER 15- 097-20,977-0000
W/2 W/2 NE, SEC. 1, T 28 S, R 16 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

3960 feet from S section line

2310 feet from E section line

Operator: CMX Inc.
Name & Address 1026 Union Center
Wichita, KS 67202

Lease Name Wotzke Well # 1

County Kiowa 155.18

Well Total Depth 4775 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 466

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:10 p.m. Day: 17 Month: 10 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4774' w/150 sx cement. Perfs at 4734-38'

1st plug sand back to 4680' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 17 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4680' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 650 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3000' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOLVED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 10-26-90

Signed [Signature]
(TECHNICIAN)

INV. NO. 29744