

1 060561

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,012-0000
150' SW C SW SE, SEC. 1, T 28 S, R 16 W/EX

560 feet from S section line
2080 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Binford "B" Well # 1

Operator: TXO Production Corp.

County Kiowa

Name & Address 200 West Douglas, Suite 300

Well Total Depth 4800 156.00 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 9 Month: May Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4787' PBD 4783' Perfs at 4677-82'

1st plug sand back to 4627' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Paul A. Luthi

Jack Luthi saw all (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 am Day: 9 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4627' and dumped 4 sx cement on top

of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125

sx cement.

STATE CORPORATION COMMISSION

5-21-85 MAY 21 1985

Maximum pressure 400 psi and shut in 300 psi

CONSERVATION DIVISION

Wichita, Kansas

Remarks: Recovered 3500' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 5-21-85

INV. NO. 8225