

To: 1 040721 12-3  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-21,043-6600 9912  
150' S of  
SW NE NE, SEC. 1, T 28 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255  
Operator: McGinness Oil Company  
Name & Address 150 N. Main, Ste. 1026  
Wichita, KS 67202

4140 feet from S section line  
990 feet from E section line  
Lease Name John Heartso Well # 1  
County Kiowa  
Well Total Depth 4812 156.39 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor McGinness Oil Company License Number 5255  
Address 150 N. Main, Ste. 1026, Wichita, KS 67202

Company to plug at: Hour: 9:45 a.m. Day: 3 Month: 12 Year: 19 92

Plugging proposal received from Keith Shahan  
(company name) McGinness Oil Company (phone) B16-269-9052

were: 5 1/2" at 4792' w/125 sx cement, Perfs at 4655-61, 4678-88'

1st plug sand back to 4600' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 150 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 3 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 6 sx cement on top of sand  
through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 5 sx gel, 50 sx cement, 5 sx gel,  
100 lbs. hulls and 150 sx cement.

Maximum pressure 500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2350' of 5 1/2" casing  
(If additional description is necessary, use BACK of this form.) 9 1992

**INVOICED**  
(do ~~not~~) observe this plugging.

DATE 1-11-93

INV. NO. 37167  
12-3-92

FEB 24 1993

Signed Stephen J. Phillips  
(TECHNICIAN)

12-9-92  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 1992