

1 030528

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21.179-~~6000~~

150' SE C SW SW SEC. 1, T 28 S, R 16 W/E

554 feet from S section line
4514 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Binford "C" Well # 1

Operator: TXO Production Corp.
Name & Address: 200 W. Douglas, Suite 300
Wichita, KS 67202

County Kiowa 158.81
Well Total Depth 4825 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 438

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor FWA Drilling Co., Inc. License Number 6165

Address P. O. Box 970, Yukon, OK 73099

Company to plug at: Hour: 5:00 pm Day: 18 Month: September Year: 19 85

Plugging proposal received from Allen Dick

(company name) TXO (phone) 316-265-9441

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1100' Elevation 2104 GL

1st plug at base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30 pm Day: 18 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement, 2nd plug at 485' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rathole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
STATE CORPORATION COMMISSION

DATE OCT 03 1985

SEP 27 1985

Signed Steve Durrant (TECHNICIAN)

INV. NO. 10348

OCT 03 1985 CONSERVATION DIVISION
Wichita, Kansas

9-27-85