


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
State Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Gray County. Sec. 3 Twp. 29S. Rge. (E) 28 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW¹/₄SW¹/₄" or footage from lines
Lease Owner Continental Oil Co.
Lease Name F.B. Wade Well No. 1
Office Address Drawer 1267 Ponca City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Nov. 10 19 51
Application for plugging filed Jan. 9 19 52
Application for plugging approved Nov. 16 19 51
Plugging commenced Nov. 14 19 51
Plugging completed Nov. 14 19 51
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Telephone Permission

Name of Conservation Agent who supervised plugging of this well C.D. Stough

Producing formation Arbuckle Depth to top 6287' Bottom 6335' Total Depth of Well 6335' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Dry	6287'	6335'	13"	435' 2"	None
				9 5/8"	1525' 10"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 1500'; set plug and cemented with 25 sacks;
filled hole with heavy mud to 250'; set plug and cemented with 25 sacks;
filled hole with heavy mud to 25' and capped with 10 sacks, plugged &
abandoned 11/14/51.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Adkins-Potter Drlg. Corp.
Address Oklahoma City, Oklahoma.

STATE OF Kansas, COUNTY OF Rice, ss.
F.L. Dunn (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F.L. Dunn*

R.F.D. #4, Lyons, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 22th day of Nov, 19 52

[Signature]
Notary Public.

My commission expires Nov. 7, 1953
FLD-AAA
STATE CORP. COMM.
TCD
FILE

23-8890-s 6-51-20M
PLUGGING
FILE NO. 3129 REV
PAGE 12 of 30

JAN 28 1953
1-28-1952

WELL LOG

CONTINENTAL OIL COMPANY

No. 1 F. B. Wade NE NE SW 3-29-28W
Gray County, Kansas

0	97	Surface Clay
97	1640	Shale & Shells
1640	1710	Anhydriate
1710	1887	Sandy Shale, Red Bed, Shells
1887	1901	Lime Anhydriate
1901	1914	Shale
1914	2377	Shale & Shells
2377	2542	Sandy Lime & Shale
2542	2586	Anhydriate
2586	2687	Anhydriate, Dolomite & Shale
2687	2774	Sandy Lime & Shale
2774	2821	Sandy Lime
2821	2945	Lime & Shale
2945	3380	Lime
3380	3435	Gray Lime, Sand & Shale
3435	4085	Lime
4085	4469	Shale & Lime
4469	5857	Lime
5857	6000	Cherty Lime
6000	6147	Lime
6147	6253	Cherty Lime
6253	6289	Sand
6289	6335	Lime
	6335	Total Depth
		Dry and Abandoned

COMMENCED: 9-12-51
COMPLETED: 11-10-51

CASINO RECORD

Set 13" surface casing
at 421' with 500 sacks
cement.
Set 9 5/8" Int. String
at 1515' with 600 sacks
cement.

STATE OF KANSAS)
)) SS
COUNTY OF RICE)

I hereby affirm that the above and foregoing is a true and correct
copy of the log of the No. 1 F. B. Wade located NE NE SW 3-29-28W, Gray
County, Kansas.

CONTINENTAL OIL COMPANY

By: *F. L. Dumm*

Subscribed and sworn to before me this 24th day of January, 1952.

R. Schmidt
Notary Public

My commission expires Nov 7, 1953

FLD-JMW
EWH
TCD
WGI
State Corp. Comm.
File

JAN 26 1952

PLUGGING
FILED 3 129 1 216
NOV 2 1952