

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Gray County. Sec. 35 Twp. 29S Rge. (E) 30 (W)

Location as "NE/CNW/SW" or footage from lines SE NW

Lease Owner Texaco Inc.

Lease Name Annah Davenport Well No. 1 "2nd Hol.

Office Address 614 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-14-19 65

Application for plugging filed Attached

Application for plugging approved Verbal 19


Plugging commenced 3-13-19 65

Plugging completed 3-13-19 65

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublett, Kansas

Producing formation Dry Hole Depth to top Bottom Total Depth of Well 5831 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dry Hole				8-5/8"	1777	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: 5831-700 w/hvy drlg mud  
700-590 w/35 sx cmt  
590-45 w/hvy drlg mud  
45-0 w/15 sx cmt.

RECEIVED  
STATE CORPORATION COMMISSION

APR 22 1965

CONSERVATION DIVISION  
Wichita, Kansas

8-22-1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
H. N. Wade (employee of owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. N. Wade Dist. Supt.

614 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 65

My commission expires 6-20-68

A. E. Boyd

Notary Public.

# WELL LOG

COMPANY **Texaco, Inc.**

SEC. 35 T. 29S R. 30W

FARM **Davenport**

NO. **1-X**

LOC. **App SE NW**


TOTAL DEPTH **5830'**

COUNTY **Gray Co., Kansas**

COMM. **2-17-65**

COMP. **3-13-65**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 1776' w/750 sx**

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 75' Surface Clay and Sand
- 240' Clay and Sand
- 500' Sand
- 675' Clay and Sand
- 1229' Red Bed
- 1420' Glorietta Sand
- 1660' Red Bed and Shale
- 1690' Stone Corral Anhydrite
- 1777' Anhydrite
- 1980' Shale
- 2170' Shale, Salt and Anhydrite
- 2420' Shale and Salt
- 2520' Lime and Shale
- 2756' Shale and Lime
- 3345' Lime
- 3415' Lime and Chalk
- 3565' Lime and Shale
- 3707' Lime and Chalk
- 3785' Lime
- 4173' Lime and Chalk
- 4325' Lime and Shale
- 4467' Lime
- 4560' Lime, Shale, and Chert
- 4755' Lime
- 4910' Lime and Shale
- 4961' Lime
- 5045' Lime and Shale
- 5139' Lime
- 5376' Lime and Shale
- 5675' Lime
- 5757' Lime, Dolomite, and Chert
- 5830' Lime
- 5830' RTD

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 22 1965

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas }  
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Davenport #1-X well.

*Sam N. Stephens*

Subscribed and sworn to before me this 25th day of March 19 65

My Commission Expires: October 19th, 1968

*David H. Freeman*  
NOTARY PUBLIC