

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-081-20,015A-
LEASE NAME Wedel 0001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
3300 Ft. from S Section Line
3300
148 Ft. from E Section Line

LEASE OPERATOR Eugene Wedel
ADDRESS Rt 2 Box 26 Copeland KS 67837
PHONE#() _____ OPERATORS LICENSE NO. _____

SEC. 15 TWP. 29 RGE. 31 (N or (W))
COUNTY Haskell

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 7-16-75
Plugging Commenced 3-2-98
Plugging Completed 3-5-98

The plugging proposal was approved on 3-2-98 (date)
by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation Council Grove Depth to Top 2662 Bottom 2672 T.D. 2856
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 3/8	1767	
				4 1/2	2850	1582


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Backed 1 1/2 off @ 1600. Mixed 1 SK hulls + 20 sx cmt. to plug perf's from 2662 to 2462. Recovered 1582 4 1/2. Circ. hole w/mud + mixed 50 sx cmt. plug from 1580 to 1430. Pulled 4 1/2 to 650. Mixed 40 sx plug from 650 + 550. Pull to 40. Mixed 10 sx plug 40 to 0. Cut off + capped 8 3/8 4 ft. below ground level.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151
Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eugene Wedel
STATE OF Kansas COUNTY OF Haskell, ss.

Eugene Wedel (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Eugene Wedel
(Address) Copeland, KS 67837



SUBSCRIBED AND SWORN TO before me this 7 day of April, 1998
Sandra J Koehn
Notary Public

My Commission Expires: 10-3-98