

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ford SEC. 15 TWP. 29S RGE. 25 ~~NW~~  
Location as in quarters or footage from lines:  
NW SE SE

			X

Locate Well  
correctly on above  
Section Platt.

Lease Owner Champlin Petroleum Company  
Lease Name Doris B. Rooney Well No. 1  
Office Address 6441 N. W. Grand, Okla City, Okla. 73116  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed 4-7-81  
Application for plugging filed 5-3-84  
Plugging commenced 5-22-84  
Plugging completed 5-22-84  
Reason for abandonment of well or producing formation Uneconomical to produce

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
Producing formation Morrow Depth to top 5264' bottom 5276' T.D. 5450'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	1190'	None
				5 1/2"	5450'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from        feet  
to        feet for each plug set.

Ran 170 jts. 4.7# tbg to 5280'. Mix 90 bbl gel mud, pump and displace to 5 1/2" csg  
down tbg. Mix and spot 50 sx Class H cement at 5280'. Pull 116 jts tbg. Mix and  
spot 50 sx Class H cement at 1650'. Pull 13 jts. Mix and spot 50 sx Class H at 1300'.  
Pull 17 jts tbg. Mix and spot 30 sx Class H at 800'. Pull 23 jts tbg. Mix and  
spot 10 sx Class H from 40' to surface. Plugging completed 6:30 pm, 5-22-84.


RECEIVED  
STATE CORPORATION COMMISSION

MAY 31 1984

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton

STATE OF Oklahoma COUNTY OF Oklahoma, ss.  
Marilyn Day (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.



(Signature) Marilyn Day  
6441 NW Grand, Okla City, Ok 73116  
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of May, 19 84

[Signature]  
Notary Public.

My Commission expires: 10-8-87

Champlin Petroleum Co.

DORIS D. ROONEY NO. 1 WELL  
 FORD COUNTY, KANSAS

OPERATIONS COMMENCED: 9/19/80

OPERATIONS COMPLETED: 10/07/80

DRILLING LOG

9/19	- 0 - 645	Sand, Gypsum
9/20	645 - 828	Sand, Gypsum, Shale
9/21	828 - 1505	Shale, Gypsum
9/22	1505 - 2200	Shale, Gypsum, Lime
9/23	2200 - 2828	Shale, Lime
9/25	2828 - 3080	Shale, Lime
9/26	3080 - 3490	Shale, Lime
9/27	3490 - 3830	Shale, Lime
9/28	3830 - 4290	Shale, Lime
9/29	4290 - 4440	Shale, Lime
9/30	4440 - 4572	Shale, Lime
10/2	4572 - 4660	Shale, Lime
10/3	4660 - 4919	Shale, Lime
10/4	4919 - 5114	Shale, Lime
10/5	5114 - 5289	Shale, Lime
10/6	5289 - 5394	Shale, Lime
10/7	5394 - 5450	Shale, Lime

CASING RECORD

9/20  
 Ran 30 jts. 8 5/8" 24# casing cement with 500 sks. Howco light sand 200 sks class H 3% C. C.

10/9  
 Ran 132 jts. of 5 1/2" casing cement with 200 sks. 50/50 poz 12 1/2# gel 18% salt.

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 08 1984

CONSERVATION DIVISION  
 Wichita, Kansas