

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-057-20291-0000

LEASE NAME Fager

WELL NUMBER #2-J

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 35 TWP. 29S RGE. 25 (X) or (W)

COUNTY Ford

Date Well Completed 12-18-82

Plugging Commenced 1-28-88

Plugging Completed 2-1-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Coastal Oil & Gas Corporation

ADDRESS 211 N. Robinson, Suite 1700, OKC, OK 73102

PHONE#(405) 239-7031 OPERATORS LICENSE NO. 6593

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5301 Bottom 5315 T.D. 5450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	oil	5301	15	8-5/8"	632	---
				5-1/2"	5437'	3227'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 5200'. Dump 20' cmt. on top. Load hole w/9.5 ppg mud. Shot @ 4,000'; 3600'; 3227'. POOH, plug #1, 40 sxs 1500'-1400', #2, 50 sxs 950'-800', #3 60 sxs 660'-510', #4, 10 sxs 40'-0'. Cutoff 8-5/8" csg. 6' BGL. Welded on steel cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Csg. Pullers License No. 672012

Address Liberal, Kansas STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

C. Brad Crouch

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Brad Crouch

(Address) 211 N. Robinson, Suite 1700, OKC, OK 73102

SUBSCRIBED AND SWORN TO before me this 11th day of February, 1988

Diana Thompson
Notary Public

My Commission Expires: Nov. 18, 1988