

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ford SEC. 35 TWP. 29S RGE. 25W E/W  
Location as in quarters or footage from lines:  
Approx. C NW NW

+			
		35	

Lease Owner Lee Banks  
Lease Name T.L.C. Well No. 1  
Office Address 200 W. Douglas, Suite 550, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry hole.  
Date Well Completed 3-25-82  
Application for plugging filed 4-8-82  
Plugging commenced 3-25-82  
Plugging completed 3-25-82  
Reason for abandonment of well or producing formation Dry hole.

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 5336'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	611'	8-5/8"	604.69'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged with 60 sacks cement at 1280';  
plug and 50 sacks cement at 600'; plug and  
10 sacks cement at 40'; and 10 sacks cement  
in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
APR - 9 1982  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing Co.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
John D. Knightley Agent (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
221 S. Broadway, Wichita, KS  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 1982

My Commission expires:



Stella J. Lipps  
Notary Public.

Lee Banks  
 200 W. Douglas, Suite 550  
 Wichita, Kansas 67202

- T.L.C. #1  
 Approx. C NW NW  
 Section 35-29S-25W  
 Ford County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
 221 S. Broadway, Suite 400  
 Wichita, Kansas 67202

Commenced: March 16, 1982  
 Completed: March 25, 1982

Drillers Log

Clay & Sand	135
Red Bed & Shale	455
Red Bed & Clay	980
Shale	1295
Red Bed & Shale	2045
Shale	2920
Shale & Lime	3930
Lime & Shale	4160
Shale & Lime	4815
Lime	5336 RTD

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR - 9 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas