

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-057-20,311-0000

LEASE NAME ASKEW

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

Ft. from S Section Line

Ft. from E Section Line

SEC. 35 TWP. 29 RGE. 25 ~~W~~ (W)

LEASE OPERATOR SPINES EXPLORATION, INC.

ADDRESS 224 EAST DOUGLAS #400 WICHITA, KS. 67202

COUNTY FORD

PHONE# (316) 264-2808 OPERATORS LICENSE NO. 7105

Date Well Completed

Character of Well OIL

Plugging Commenced 2-14-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-25-91

The plugging proposal was approved on FEB. 7, 1991 (date)

by DAN GOODROE (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5419

PERFORATIONS: 5300-5310.  
Show depth and thickness of all water, oil and gas formations.

RECEIVED

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
		0	650	8 5/8	650	0
		0	5411	5 1/2	5411	2548

MAR - 7 1991

CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

2-14-91: ELECTRA SET PERM. WIRE LINE PLUG AT 5200, PUMPED 25 SX CEMENT ON TOP OF PLUG.  
SHOT OFF CASING AT 2548, PULLED CASING.

2-25-91: TOP HOLE PLUG, 300# HULLS, 15 SX. GEL, 50 SX. CEMENT, 10 SX. GEL, 100# HULLS,  
8 5/8 PLUG, 175 SX. CEMENT, 60-40-POZ, 6% GEL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: SPINES EXPLORATION, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY

OF PLUGGING CONTRACTOR.

(Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P O Box, Inc.



SUBSCRIBED AND SWORN TO before me this 6th day of March, 1991

Dorothy M. Ferguson

Notary Public

My Commission Expires February 6, 1993