

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-057-20,255-0000

LEASE NAME ASKEW

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. TWP. RGE. (E) or (W)

COUNTY FORD

LEASE OPERATOR SPINES EXPLORATION INC.

ADDRESS 224 EAST DOUGLAS #400 WICHITA, KS. 67202

PHONE# (316) 264-2808 OPERATORS LICENSE NO. 7105

Character of Well GAS

Date Well Completed

Plugging Commenced 2-11-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-25-91

The plugging proposal was approved on Feb. 7, 1991 (date)

by DAN GOODROE (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 5400

PERFORATIONS: 5267-73 w/ 2 s p f.
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
		0	608	8 5/8	608'	0
		0	5399	5 1/2	5399	2787'

MAR - 7 1991

CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

2-13-91: ELECTRA LOG SET PERM WIRE LINE PLUG AT 5200', PUMPED 25' SX CEMENT ON TOP OF PLUG.
 2-25-91: TOP HOLE PLUG, 300# HULLS, 15 SX. GEL, 50 SX. CEMENT, 10 GEL, 100# HULLS, 8 5/8 PLUG, 175 SX. CEMENT. 60-40 POZ, 6% GEL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: SPINES EXPLORATION INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR.

(Employee of ~~XXXXXXXXXXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) To PWS, Inc.



SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 91

Dorothy M. Ferguson
 Notary Public

My Commission Expires: February 6, 1993