



King "C" #1

Drilg. Comm: 4-29-50  
 Drilg. Comp: 5-12-50  
 Drilg. By: Mine Drilg. Inc.

Loc: 330'N, 990'E of N.E. Cor.  
 Elev: 1426 R.T.B.  
 Note: All measurements taken from R.T.B.

T. D. 3842'

R.T.B. 3842

I. P. D & A (May 12, 1950, P & A)

Top Brown Ls. 2857 No oil noted.  
 Base 2869

Casing Records:  
 8 5/8" set at 211'; cas. w/150 cas.

Top Lansing Ls. 3096  
 Base 3353 No oil noted.

Straight Hole Surveys: (2yfe)  
 500' O.K. 3000' O.K.  
 1000' O.K. 2800' O.K.  
 1500' O.K. 3250' O.K.

Top Miss Chat 3730  
 3730-43 Cherty Congl., all stain, N.S.F.O.  
 3743-98 Cherty Ls., N.S.O.

Steel Line Measure

225 = 225	2807 = 2805
1100 = 1100	3647 = 3645
1500 = 1500	3735 = 3733
2355 = 2360	3793 = 3798

DST #1 3735-98  
 Packer set at 3735  
 Open 45 minutes - all blow for 15 min.,  
 then dead.  
 Closed 15 minutes for B.H.P.

Results:

14' Rotary Drilg. Mud  
 500' B.H.P.

Formation Records:

200 Surface clay, shale & shells  
 211 Shale & shells  
 520 Shale  
 680 Shale & shells  
 995 Lins  
 1110 Shale & Lins  
 1275 Lins  
 1450 Lins & Shale  
 1955 Shale  
 2060 Lins  
 2600 Shale & Lins  
 2770 Lins  
 2960 Lins & Shale  
 3060 Lins  
 3130 Shale & Lins  
 3335 Lins  
 3390 Lins  
 3474 Lins & Shale  
 3580 Lins  
 3715 Shale & Lins  
 3827 Lins  
 3842 Chert

3798-3814 Cherty Ls. N.S.O.  
 3814 - 26 Dol., cherty, stain in dol. & chert  
 (no free oil in cuttings)  
 3826-42 Ls., cherty, hard, N.S.O.

DST #2 3800-42

Packer set at 3800  
 Open 45 minutes - steady blow increased for  
 45 minutes  
 Closed 15 minutes for B.H.P.

Results:

180' sandy salty str.  
 1274# B.H.P.

T.D. 3842

P & A May 12, 1950.

RECEIVED

Conservation Div.

JUN 14 1950

STATE CORPORATION  
 COMMISSION  
 KANSAS

PLUGGING  
 FILE NO. 29-27-47  
 BOOK PAGE 10 LINE 23

T. D. 3842