

R

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 18 Twp. 27 Rge. (E) 4 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Shawver Armour, Inc.
Lease Name Northcutt # Well No. 1
Office Address 817 Central Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 2 1965
Application for plugging filed March 2 1965
Application for plugging approved March 2 1965
Plugging commenced March 2 1965
Plugging completed March 2 1965
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4131 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	-0-	222	8 5/8	222	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole with 40 vis. mud to 225 ft.
Set a dry hole plug - added 1/2 sack of hulls and 20 sacks cement.
Mudded hole from this point to 30 ft. set a plug - added 1/2 sack hulls and 8 sacks cement.
Mudded rat hole to 10' of surface and dumped 2 sacks cement. 222' of 8 5/8" surface pipe cemented 250 sacks.

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1965

3-12-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shawver Armour, Inc.
Address 817 Central Building Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James M. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour (James M. Armour)
817 Central Bldg. Wichita, (Address)

SUBSCRIBED AND SWORN to before me this 10th day of March, 1965

My commission expires December 10, 1967
Claire Jones Notary Public.

6

D R I L L E R ' S L O G

FARM NAME: NORTH CUTT #1 LOCATION: NW NW SW Sec. 18-27-4W
 Sedgwick, County
 CONTRACTOR: SHAWVER ARMOUR, INC.
 OWNER: SHAWVER ARMOUR, INC. ELEVATION: 1439 K. B.
 COMMENCED: February 17, 1965 COMPLETED: March 2, 1965
 CASING RECORD: 222' 8 5/8" w/250 sacks cement & 6 sacks CC

FORMATION:

Earth, Sand & Shale 0-222
 Gray Shale 500
 Dark Shale 650
 Lime & Shale 725
 Shale & Lime 2620
 Lime & Shale 2802
 Shale & Lime 2871
 Kansas City Lime 2906
 Lime 3359
 Lime & Shale 3690
 Mississippi Chert 3711
 Mississippi Dolomite 3730
 Lime 3984
 Shale 4102
 Simpson Sand 4112
 Rotary Total Depth 4131

TOPS:

Heebner 2620
 Douglas Shale 2703
 Brown Lime 2832
 Lansing 2867
 Rework Mississippi 3690
 Mississippi Dolomite 3712
 Viola 4102
 Simpson 4112

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 12 1965
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 SEDGWICK COUNTY) ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour
 James M. Armour

Subscribed and sworn to before me this 10th day of March 1965.

My commission expires Dec. 10th, 1967

Claire Jones
 Claire Jones Notary Public