

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate well correctly on above
Section Plat

Sedgwick County. Sec. 5 Twp. 27S Rge. 4 ~~NE-NE-SW~~ (W)
Location as "NE/CNW/SW" or footage from lines NE-NE-SW
Lease Owner Fleming & Woodman Drlg. Co. & Frank A. Oyster
Lease Name WALTJ Well No. 1
Office Address Box 536, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-18-55 19
Application for plugging filed 5-18-55 19
Application for plugging approved 5-18-55 19
Plugging commenced 5-18-55 19
Plugging completed 5-18-55 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lay down drill pipe and mixed heavy mud in hole.
Ran bridge plug at 252 feet. Ran 15 sacks cement
and filled hole to 10 feet below cellar. Plug
and 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Fleming & Woodman Drilling Company
Address Box 536, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
K. T. Woodman (employer of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman
921 Union National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 55.

My commission expires Dec. 22, 1958.

Evelyn R. North
STATE CORP. Notary Public.

24-2675-S 2-52-20M

MAY 20 1955

5-20-55

PLUGGING
FILE SEC 5 27 D. 4w
BOOK PAGE 20 LINE 9

CONSERVATION DIVISION
Wichita, Kansas

DRILLING LOG

Company: Fleming & Woodman Drilling Company
and Frank A. Oyster, et al

Lease: WALTY - NE-NE-SW 5-27S-4W, Sedgwick County, Kansas.

Well: #1

Contractor: Fleming & Woodman Drilling Company
Box 536, Great Bend, Kansas

Date Comm: 5-1-55
Date Compl.: 5-18-55

T. D.: 4087'

Casing: 252' 8-5/8" surface casing.

TOPS: Elevation: 1407 R. B.
Brown Lime: 2780 1378
Stalnaker Sand: 2795 1388
Lansing: 2819
Mississippi: 3637
Kinderhook: 2927
Viola: 4053
Simpson Sandy
Shale: 4066


Figures Indicate Bottom of Formation

| | | | |
|------|----------------|------|--------------|
| 0-40 | Surface Soil | 1470 | Lime & Shale |
| 90 | Sand | 1680 | Shale & Lime |
| 160 | Shale & Shells | 1910 | " " |
| 252 | " " | 2075 | " " |
| 325 | " " | 2215 | " " |
| 600 | " " | 2320 | Lime & Shale |
| 690 | Salt and Shale | 2455 | " " |
| 750 | " " | 2520 | Shale & Lime |
| 865 | Lime & Shale | 2640 | " " |
| 905 | " " | 2760 | Lime & Shale |
| 960 | " " | 2840 | " " |
| 1065 | " " | 2882 | Lime |
| 1235 | " " | 2930 | " |
| 1360 | " " | 2985 | " |

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1955

CONSERVATION DIVISION
Wichita, Kansas



Page 2. DRILLING LOG

Walty #1

NE-NE-SW 5-27S-4W, Sedgwick County, Kansas.

| | | | |
|-----------|--------------|------|------------------------------------|
| 2985-3030 | Lime | 3560 | Lime & Shale |
| 3073 | " | 3637 | " " |
| 3110 | " | 3650 | Mississippi CHERT Chert |
| 3165 | " | 3685 | " |
| 3180 | " | 3730 | " " |
| 3240 | " | 3750 | " |
| 3285 | " | 3795 | Shale & Chert |
| 3290 | " | 3827 | Lime & Chert |
| 3322 | Shale & Lime | 3850 | " " |
| 3375 | Lime & Shale | 3890 | Shale & Chert |
| 3420 | " " | 3918 | " " |
| 3470 | " " | 3955 | " " |
| 3530 | " " | 4020 | Lime & Shale |
| | | 4060 | " " |
| | | 4087 | " " T. D. |

I certify the above to be true and correct to the best of my knowledge and belief.

FLEMING & WOODMAN DRILLING COMPANY

By: K. T. Woodman
K. T. Woodman

Subscribed and sworn to before me this 19th day of May, 1955.

Evelyn V. North
Notary Public

My commission expires Dec. 22, 1958.