

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Kiowa County, Sec. 2 Twp. 29S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines NW NE

Lease Owner Mull Drilling Company

Lease Name Ralstin Well No. 1

Office Address 1625 Wichita Plaza, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 26 19 66

Application for plugging filed April 26 19 66

Application for plugging approved April 26 19 66


Plugging commenced April 26 19 66

Plugging completed April 26 19 66

Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation -- Depth to top -- Bottom -- Total Depth of Well 5070 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	289.28'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 275'. Cement through drill pipe with 25sacks. Mud back to 40', set solid bridge and capped with 10 sacks. 2 sacks in rat hole. Plugging completed at 12:15 P.M. 4-25-66.

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1966
CONSERVATION DIVISION
Wichita, Kansas

5-3-1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains

1425 Wichita Plaza, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 19 66

My commission expires March 3, 1970

Mary J. Brown
Notary Public.

ROTARY DRILLING LOG

Operator: Mull Drilling Company, Inc.
#1 Ralstin
NW NE Section 2-29S-20W
Kiowa County, Kansas

Contractor: Rains & Williamson Oil Co.
Commenced: 4-9-66
Completed: 4-26-66

Remarks: Set 289.28' of 8-5/8" surface casing with 275 sacks of GL3.

FORMATIONS:

Shale	110'
Sand	140'
Shale	545'
Anhydrite	561'
Shale	691'
Red Bed & Shale	1282'
Anhydrite	1326'
Shale	1335'
Shale & Lime	1665'
Shale	1880'
Shale & Lime	2440'
Lime	2712'
Lime & Shale	3350'
Shale & Lime	3578'
Lime & Shale	4010'
Shale & Lime	4090'
Lime & Shale	4240'
Lime	5070'
Rotary Total Depth (D&A)	5070'

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1966
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 28th day of April, 1966.

My Commission Expires:
March 3, 1966

Mary J. Brown
Mary J. Brown, Notary Public