

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa

County, Sec. 2 Twp. 29S Rge. (E) 20(W)Location as "NE/CNW/SW" or footage from lines C NE SWLease Owner Mull Drilling Company, Inc.Lease Name MORFORD Well No. 1Office Address 1625 Wichita Plaza - Wichita, KansasCharacter of Well (completed as Oil, Gas or Dry Hole) Dry HoleDate well completed 12-3 19 68Application for plugging filed 12-3 19 68Application for plugging approved 12-3 19 68Plugging commenced 12-3 19 68Plugging completed 12-3 19 68Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.If a producing well is abandoned, date of last production 19Was permission obtained from the Conservation Division or its agents before plugging was commenced? YesName of Conservation Agent who supervised plugging of this well Ralph Warren, Pratt, KansasProducing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5105 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	484'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud at 285'. Set solid bridge of hulls and plug. Capped with 25 sacks cement. Filled up to 40', built solid bridge, hulls and plug. Capped with 10 sacks, 2 sacks in rat hole. Completed 7:00 PM 12-3-68.

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.Address 1425 Wichita Plaza - Wichita, KansasSTATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza - Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of December, 19 68My commission expires 6-30-71

Sherry Gish

Notary Public.

ROTARY DRILLING LOG

Operator: Mull Drilling Company, Inc.
 MORFORD #1
 C NE SW 2-29S-20W
 Kiowa County, Kansas

Contractor: Rains & Williamson
 Oil Co., Inc.

Commenced: 11-19-68

Completed: 12-3-68

Casing: 8-5/8" @ 484'/260 sx.

Formations

Shale and Sand	491'
Shale	508'
Red Bed	571'
Blaine Anhydrite	586'
Shale and Shells	920'
Shale	1300'
Anhydrite	1342'
Shale and Red Bed	1420'
Shale	2273'
Shale and Shells	2410'
Lime and Shale	4470'
Lime	5105'

Rotary Total Depth (D & A) 5105'


RECEIVED
 STATE CORPORATION COMMISSION
 DEC 13 1968
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is
 true and correct to the best
 of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


 Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the
 State of Kansas, County of Sedgwick, this 11th day of December, 1968.


 Sherry Gish Notary Public

My Commission Expires:
 June 30, 1971