


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kiowa County. Sec. 12 Twp. 29 S Rge. 20 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SE  
Lease Owner Pickrell Drilling Company  
Lease Name Rader Well No. 1  
Office Address 705-4th Nat'l. Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-21 19 58  
Application for plugging filed 12-21 19 58  
Application for plugging approved 12-21 19 58  
Plugging commenced 12-21 19 58  
Plugging completed 12-21 19 58  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. Lac Kamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5127 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 297'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 295', bridge hole and cement with 20 sacks cement.  
Thn heavy mud to 30' below ground level, bridge hole and cement with 10 sacks cement to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 9 1959  
CONSERVATION DIVISION  
Wichita, Kansas  
1-9-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
C. W. Sebitts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of December, 19 58

My commission expires May 13, 1962  
Mary Ellen Sampson Notary Public.

PLUGGING  
FILE SEC 12 T. 29 R. 20  
BOOK PAGE 9 LINE 39

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 12-2-58

LOCATION: SE SE SE Sec. 12-29S-20W  
Kiowa County, Kansas

Rotary Drilling Completed 12-21-58

#1 Rader

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: 8-5/8" 28# Lapweld 8 thd (used) (14 jts) Casing set at 297' with  
150 sacks cement, 2% Gel. Cement circulated.

(No 5-1/2" casing -- Dry Hole)

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

|                 |            |                      |       |
|-----------------|------------|----------------------|-------|
| Top soil & Clay | 84'        | Circ. for samples at | 4723' |
| Sand & Gravel   | 150'       |                      | 5020' |
| Blue Shale      | 297'       |                      | 5042' |
| Blue Shale      | 450'       |                      | 5052' |
| Red Beds        | 635'       |                      | 5065' |
| Anhydrite       | 690'       |                      | 5075' |
| Red Beds        | 1075'      |                      | 5088' |
| Shale & Shells  | 1640'      |                      | 5125' |
| Lime & Shale    | 2451'      |                      |       |
| Lime            | 3340'      |                      |       |
| Shale & Lime    | 3815'      |                      |       |
| Lime            | 5040'      |                      |       |
| Mississippi     | 5062'      |                      |       |
| Lime            | 5065'      |                      |       |
| Mississippi     | 5108'      |                      |       |
| Lime            | 5125' T.D. |                      |       |

S.L.M. at 2950 - O.K.  
4000 - O.K.  
4600 - O.K.

Slope Test at 2000 0° off  
3000 0° off  
4000 0° off

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 9 1959  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 12 T 29 R 20W  
BOOK PAGE 9 LINE 39

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By

Attorney-in-Fact

STATE OF KANSAS

COUNTY OF SEDGWICK

ss.:

On this 29th day of December, 1958, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. SEBITS to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 13, 1962

Mary Ellen Sampson  
Notary Public

(Mary Ellen Sampson)