

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-097-21-190-0000

LEASE NAME RICHARDSON-ALBERTS

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 12 TWP. 29 RGE. 20W (E) or (W)

COUNTY KIOWA

LEASE OPERATOR J. MARK RICHARDSON

ADDRESS 155 N MARKET #840 WICHITA KS 67202

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 11/85

Plugging Commenced 2/20/96

Plugging Completed 2/22/96

The plugging proposal was approved on 2/20/96 (date)

by STEVE PENDLETON (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation MISS Depth to Top 4760 Bottom 5060 T.D. 5185

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD 3-1-1996

Formation	Content	From	To	Size	Put In	Pulled out
MISS		0	353	13 3/8	353	0
		0	5799	4 1/2	5799	590

Describe in detail the manner in which the well was plugged, indicating where the mud plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
sand off 4 1/2 cs to 4700' dump bail, 4 sk cement on top of sand
take free point cut 4 1/2 cs @ 600' pull & lay down 600' 4 1/2 cs run T.
to 600 ft pump 3 sk gel 50 sk cement, pull T to 360' pump 50 sk
cement, put 15 sk cement @ 60; cs stayed full
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GREENSBURG WELL SERVICE License No. 31201

Address 303 E KANSAS GREENSBURG, KS. 67054

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J. MARK RICHARDSON

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

J. MARK RICHARDSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 155 N MARKET #840 WICHITA KS 67202

SUBSCRIBED AND SWORN TO before me this 8TH day of MARCH, 19 96



Kim Santella
 Notary Public

My Commission Expires: _____