

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 097-21,269-0000

LEASE NAME MILLER

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR J. MARK RICHARDSON

SEC. 17 TWP. 29 RGE. 20W (E) or (W)

ADDRESS 55 N. MARKET SUITE 840 WICHITA, KS. 67202

COUNTY KIOWA

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Date Well Completed 3/89

Character of Well OIL

Plugging Commenced 8/24/92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/4/92

The plugging proposal was approved on 8/4/92 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation MISSISSIPPI Depth to Top 5114 Bottom 5135 T.D. 5240

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
MISS	OIL	0	612	8 5/8	612	0
		0	5240	4 1/2	5240	3520

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

sand off perf. to 5100 ft; dump bail 4 sk cement, take free point cut and pull 3550 ft of 4 1/2 cs. pump 300# hulls, 10 sk gel, 50 sk cement, 10 gel, 100# hulls 8 5/8 plug 150 sk cement, all cement 60/40 pox 6 % gel max press 500# ISIP 150# 15 sk cement down water well.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GREENSBURG WELL SERVICE License No. RECEIVED ^(same as above)

Address 303 E. KANSAS GREENSBURG, KS. 67054 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J. MARK RICHARDSON **SEP 18 1992**

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

CONSERVATION DIVISION
Wichita, Kansas

J. MARK RICHARDSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Mark Richardson

(Address) 175 N. MARKET SUITE 804, WICHITA, KS.

SUBSCRIBED AND SWORN TO before me this 16TH day of SEPT., 19 92

Kim Santellan
Notary Public

My Commission Expires: _____

