

1 120019  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corporation  
Name &  
Address 155 North Market, Suite 1000  
Wichita, KS 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2:30 p.m. Day: 22 Month: 9 Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 3636' PBTD 2953' Perfs at 3409-13, CIBP at 3400', 2878-82'

1st plug pump 2 sx hulls and 25 sx cement,

2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 22 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 200 lbs. hulls, 25 sx cement and pushed plug to 2820',

2nd plug pumped in 8 5/8" casing with 300 lbs. hulls, 10 sx gel, 50 lbs. hulls, 50 sx cement, 10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

Pumping pressure 200-500 psi and shut in 350 lbs.

Remarks: Used 60/40 Pozmix 4% gel by B.J. Titan. Recovered 1300' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

**INVOICED** (operator) observe this plugging.

DATE 10-7-87

INV. NO. 18408

Signed Paul Luthi  
(TECHNICIAN)

9-22-87

API NUMBER 15-097-20,434-A <sup>0001</sup>

NE SW SW, SEC. 32, T. 29 S, R. 17 W/E

840 feet from S section line

4580 feet from E section line

Lease Name Schwarm OWWO Well # A-1

County Kiowa 129.26

Well Total Depth 3693 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 460

SEP 29 1987  
9-29-1987

CONSERVATION DIVISION  
Wichita, Kansas

Q