

1070110

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-21,397-0000
E/2 NE SE SEC. 32, T 29 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 375 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SCHWARM WELL # 1-32

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 162.50

OPERATOR LICENSE # 5086

WELL TOTAL DEPTH 5000 FEET

OPERATOR: PINTAIL PETROLEUM LTD PRODUCTION CSG: SIZE 5 1/2" @ 4994' WITH SX

NAME AND ADDRESS 225 N MARKET, SUITE 300 SURFACE CASING: SIZE 8 5/8" @ 463' WITH SX

WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREBINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DR. STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 24 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4924

1ST PLUG SAND BACK TO 4846'. DUMP 5 SX CEMENT WITH BAILER. 2ND PLUG SPOT 10 SX GEL &

50 SX CEMENT AT 1050'. 3RD PLUG SPOT 50 SX CEMENT AT 490'. 4TH PLUG SPOT 10 SX CEMENT

AT 0-40'.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 AM DAY: 24 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND BACK TO 4846'. DUMP 5 SX CEMENT WITH BAILER. 2ND PLUG SPOT 10 SX GEL AND

50 SX CEMENT AT 1050'. 3RD PLUG SPOT 50 SX CEMENT AT 490'. 4TH PLUG SPOT 10 SX CEMENT

AT 0-40'. GOOD CIRCULATION THROUGHOUT JOB.

INVOICED

RECEIVED DEC 08 1999

DATE 12/21/99

12-8-1999

NO. 061001

CONSTRUCTION DIVISION WICHITA, KS

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3325' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID)OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3