

1030232

15-097-20190-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,190
C SE , SEC. 10 ; T 29 S, R 17 (W/X)
660 feet from ~~XXX~~ SE Corner of section line
660 feet from ~~XXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5237

Lease Name Conklin Well # 1-10

Operator: Plano Petroleum Company

County Kiowa

Name & Address P. O. Box 247

Well Total Depth 2950 95.88 feet

Plano, TX 75074

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 351

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 am Day: 26 Month: July Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 2948' PBSD 2916' Perfs 2909-13'

1st plug pump 35 sx cement and plug to 2860'

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 125 sx cement.

Plugging Proposal Received by Steve Shumway
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: noon Day: 26 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 2948' PBSD 2916' Perfs 2909-13'

1st plug pumped 35 sx cement and plugged to 2860', 2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 1822' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 8-13-84

Signed Steve Shumway
AUG 01 1984 (TECHNICIAN)

INV. NO. 2992

AUG 22 1984

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84