

1060254

15-097-30119-
0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 11-10-65-
C SW NE SW SEC. 16, T 29 S, R 19 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

_____ feet from N/S section line
_____ feet from W/E section line

Operator: Graham-Michaelis Corporation

Lease Name Thach Well # 1-16

Name & Address P. O. Box 247

County Kiowa

Wichita, KS 67201

Well Total Depth 5130 ^{166.73} feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 618

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 560, Liberal, KS 67901

Company to plug at: Hour: noon Day: 27 Month: June Year: 19 84

Plugging proposal received from Bob Sargent

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2 set at 5129' Perfs 5077-5103'

1st plug pump 1 sack hulls and 25 sx cement on bottom through bailer

2nd plug at 1400' with 40 sx cement

3rd plug at 668' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:00 pm Day: 27 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 5129' Perfs 5077-5103'

1st plug pumped 1 sack hulls and 25 sx cement on bottom through bailer, 2nd plug at 1400'

with 40 sx cement, 3rd plug at 668' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: They recovered 2621' of 4 1/2" casing. Used common sacked cement by Sargent's.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

I (did / did not) observe this plugging.

Signed Paul A. Luthie
(TECHNICIAN)

DATE 7-16-84

JUL 06 1984

INV. NO. 2499

7-6-1984

6-27 JUL 17 1984

CONSERVATION DIVISION
Wichita, Kansas